

Box 100 | 7400 Prospect Street Pemberton BC VON 2L0 P: 604.894.6135 | F: 604.894.6136 Email: admin@pemberton.ca Website: www.pemberton.ca

INSPECTIONS

It is the permit holder's responsibility to call for inspections and ensure that all inspections are carried out. Generally requests must be received at least 24 hours in advance of the desired inspection date.

When booking an inspection please provide staff with a contact name, telephone number, address of construction, type of inspection requested, permit number and the date the inspection is being requested.

	Please have a set of approved plans on site for all inspections
V	
	Site Survey
	Non-Encroachment Certificate (Form Inspection) may be required to confirm minimum set-backs
	Final Surveyed Site Plan will be required prior to framing inspection which may include elevation survey.
	Include elevation survey.
	Footings/Foundation – After the forms for footings and foundations are complete, but prior to placing
	of any concrete therein. Sealed Structural Engineer Inspection report is required.
	Damp proofing/Drain tiles - After removal of form-work from a concrete foundation and installation of
	perimeter drain tiles and damp proofing, but prior to back-filling against foundation.
	Water & Sewer Connections- An as-built drawing must be filed with the Village before the connection
	can be inspected, backfilled and the water turned on
	Underground Rough-in Plumbing – Before a building drain, sanitary or storm sewer is covered. If any
	part of the plumbing system is covered before it is inspected and approved, it shall be uncovered if the
	Building Inspector so directs, and when considered necessary, underground building drains, branches,
	storm drains, and sewers shall be re-tested after the completion of all back-filling and grading by heavy
	equipment.
	Pre-slab - After the 6 mil (UV rated) poly is placed over the compacted gravel base of the concrete
	slab but prior to any concrete being placed for the floor.
	Water test & Rough in Plumbing - After all supply and DWV (drain, waste & vent) piping is installed
	and ready to be tested with water and/or air, but prior to any covering up or concealment of any kind.
	Hydronic heating documents to be submitted (if applicable).
	Water Meter Inspection
	Sprinkler Inspection-If applicable
	Trip test is required for dry system/Alarm Test for wet system
	Ventilation Checklist-Check list to be signed off by TECA Ventilation Professional and submitted prior
	to Framing Inspection
	Framing - After framing and sheathing of the building are complete, including fire-stopping, bracing,
	chimney, duct-work, plumbing, gas venting, wiring, but before any insulation, lath, or other interior or
	exterior finish is applied that conceals such work. Sheathing is part of the framing inspection may be
	done prior to the framing inspection.
	Ventilation checklist
	Tub & Shower Installation and Testing
	Insulation/poly vapor barrier - After all insulation and 6 mil polyethylene (UV-rated) is installed,
	(including floor joist-end cavities, crawlspace foundation insulation and attic insulation), but prior to any
	interior finish or other concealment is applied.
	Woodstove/Fireplace/Chimney - When applicable, factory-built chimneys and fireplaces and solid
	fuel burning appliances are roughed-in; or in the case of masonry fireplace or chimney construction,
	when the smoke shelf is complete and the first two (2) flue liners are in place.
	Building Final – After the building or portion thereof is complete and ready for occupancy, but before
	occupancy takes place of the whole or portion of the building. Please ensure that all engineer
	Schedules have been received by the inspector two days before calling for your final building inspection.